Human Appeal - Sudan	
BOQ for	Al Shorouq TEVT Training Center
Date of BoQ	46294
HA - Sudan Omdurman, Khartoum State office	

#	Items	Unit	Quantity	Unit Cost (SDG)	Total Cost SDG
1	Supplying and excavating a strip foundation and building the wall of the fence from concrete block with a height of 70 cm with finishing and completing the fence with a height of 1 meter with the making of piles every 3 meters of concrete block, brick and half with a height of 2 meters with whiteness and final finishing, and the price includes the supply, manufacture and installation of doors of square pipes with dimensions of 3 * 2 meters with the work of the pillars of fixation and final finishing	L.M.	115		
2	Supply, drilling, building and finishing a stabilized protection platform for the center body with a height of 40 cm with the work of backfills and white concrete 7 cm thick with the making of separators for expansion every 1 meter and finishing	L.M.	55		
3	Supply, Audit and Rehabilitation of Electricity Connections	Item	1		
4	Rehabilitation of whiteness and cracks	Item	1		
5	Making Paint or its equivalent in quality with the foundation layer for the walls inside and out, and the colors will be chosen by the supervising engineer	M2	68.75		
6	Making Texture Paint or its equivalent in quality with the foundation layer for the walls inside and out, and the colors will be chosen by the supervising engineer	M2	304.5		
7	Supply, maintenance, rehabilitation and finishing of doors and windows	Item	1		
8	Supply, rehabilitation and maintenance of toilets and the price includes finishing, maintenance, manufacture and installation of doors with the supply and installation of ventilation pipes	Item	1		

9	Making an umbrella of square pipes size 4 x 8 thickness 1.2 mm and American zinc with the construction of a wall with a height of 5 meters according to the attached map, with the supply and installation of two doors of square pipes, baffling sheet with dimensions of 1.20 * 2.20, windows with dimensions of 1 x 1.2 meters of square pipes, baffling sheet, skylights with dimensions of 1 * 1.2 seconds with the work of pouring floors with white concrete and floor tiles with Abyssinian tiles thickness of 20 mm with dimensions of 30 x 30 cm and making roofs of American zinc and a roof borrowed from wood Bamboo with insulation work and the price includes the supply and installation of two 6000 water conditioners, 8 4 double feet bulbs, 3 full Indian Orient fans, and the final finishing with the engineer's wire pomastic, according to the origin of the workmanship and the instructions of the supervising engineer	M2	72		
	Total Cost				

Eng. Abdelrahman Elfaki

Note: Contractors must visit the site: Al Shorouq Area, Haj Yousif, East Nile, Khartoum State